BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT17891

APPROVED SCHEDULE - B

EE/RTP/BBMP/E-PMT/01/2015-16

Improvements to Roads and Drains in Varma Layout Amruthahalli in Ward No 07, Kodigehalli Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NINGANAGOWDA V PATIL		
				In Figures		In Words
1	906.75	KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications.	cum	75.0	68006.25	Rupees Seventy Five Only
2	3220.80	Removing BS Slab of drain and stacking.	sqm	57.0	183585.6	Rupees Fifty Seven Only
3	2898.72	Refixing stone slabs of drains and pointing in CM 1:3.	sqm	75.0	217404	Rupees Seventy Five Only
4	322.08	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. (7.50cms thick)	sqm	635.0	204520.8	Rupees Six Hundred Thirty Five Only
5	6.30	Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing	cum	5050.0	31815	Rupees Five Thousand Fifty Only
6	15.12	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	cum	3830.0	57909.6	Rupees Three Thousand Eight Hundred Thirty Only
7	25.02	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour	sqm	238.0	5954.76	Rupees Two Hundred Thirty Eight Only
8	9.66	Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges)Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-3320Kg/cum) (P. 18, I.No. 4.49.1) SR-2014-15	cum	5840.0	56414.4	Rupees Five Thousand Eight Hundred Forty Only
9	0.77	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery	TONNE	78000.0	60060	Rupees Seventy Eight Thousand Only
10	87.00	KSRRB M300. Construction of Embakment with material Grave /murrum. Construction of Embakment with approved material gravel/murrum with all lifts and leads, transporting to site, spreading grading to requiered slope and compacting to meet requirement Table 300-2 complete as per specificcation (Which include cost of gravel / murrum watering charges & compaction by vibratory roller)	cum	221.0	19227	Rupees Two Hundred Twenty One Only

ಸ.ಅ. (ಪೂ.ವ) 26/2/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NINGANAGOWDA V PATIL		
				In Figures		In Words
11	6325.40	KSRRB M300-52.1. Scarifying the existing granular road surface to a depth of 50mm and disposal of scarified material within all lifts and leads upto 1000 metres complete as per specifications	sqm	18.0	113857.2	Rupees Eighteen Only
12	6325.40	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery	sqm	4.0	25301.6	Rupees Four Only
13	948.81	KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. (P. 154 Item No. 20.18)14-15	CUM	1430.0	1356798.3	Rupees One Thousand Four Hundred Thirty Only
14	6325.40	KSRRB M500-6. Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications.	sqm	31.0	196087.4	Rupees Thirty One Only
15	189.76	KSRRB M500-18. Providing and laying semi dense bituminous concrete25mm to 30mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.8 complete in all respects as per specifications. with 80/100 grade bitumen using 40-60 HMP using mechanical paver	cum	8470.0	1607267.2	Rupees Eight Thousand Four Hundred Seventy Only
16	195.20	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications.	sqm	475.0	92720	Rupees Four Hundred Seventy Five Only
17	906.75	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km (	cum	140.0	126945	Rupees One Hundred Forty Only
					4423874.11	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

26/2/16